Abstract For Proposed Building Interior Work @ Perambalur				
S.No	Description	Quantity	Amount	Remarks
1	CUPBOARD (2'6"*2'0"*1'0") - 19mm & 8mm Waterproof ply to be used with Mica Finishing. *Hydraulic hinges to be used	1.00	9,850.00	
2	CUPBOARD (2'0*1'9"*1'0") - 19mm & 8mm ply to be used with Mica finishing. *Hydraulic hinges to be used	1.00	9,650.00	
3	CUPBOARD (6'0"*4'6"*1'3") - 19mm Commercial ply & 6mm water proof ply to be used with Mica finishing.	1.00	30,375.00	
4	TV Unit (4'6"*5'6") - 19mm & 8mm ply to be used with Mica finishing.	1.00	4,912.00	
5	Footwear (4'0"*3'0"*2'0") - 2No's (4'0"*1'6"*1'0") - 1 No's - 19mm readymade plywood to be used with Mica finishing.	1.00	12,000.00	
6	EB Box Rework (Mica laminating)	1.00	4,350.00	
7	Toilet Frame (4'0"*2'0") - 19mm ply & 6mm waterproof Plywood to be used with Mica finishing	1.00	6,850.00	
8	COACH Mica laminate modifications (3 doors only)	1.00	2,000.00	
9	Total		79,987.00	